

Estimate: basement rebuild after water loss

Estimate no. NR-2291 · September 30, 2026

PREPARED FOR Chinedu and Amara Okafor 2620 Central Park Ave, Evanston, IL 60201 Antsurance claim, loss date September 21, 2026	SITE VISIT September 29, 2026, with the homeowner, after drying was signed off by Lakeshore Restoration. AREA Finished basement, 1,150 sq ft, including one bathroom
--	---

SCOPE OF WORK	AMOUNT
1 Site protection, remaining demolition and prep Remove damaged door casings and vanity base, protect stairs, daily cleanup.	\$1,850.00
2 Framing repair and insulation Replace two sections of bottom plate, R-13 batts at exterior walls, 296 sq ft.	\$2,400.00
3 Drywall Hang, tape and finish the 4 ft flood cut on 148 lin ft of wall, plus bathroom walls. Level 4 finish.	\$4,150.00
4 Flooring Luxury vinyl plank with moisture barrier, 1,150 sq ft at \$6.80, replacing carpet and laminate.	\$7,820.00
5 Trim and doors Baseboard throughout, three interior doors with casing and hardware.	\$2,960.00
6 Bathroom New vanity and top, reset toilet, replace supply lines with shutoff valves, repair floor tile.	\$3,480.00
7 Electrical Replace nine receptacles below the water line, add GFCI protection at the bath. Licensed subcontractor.	\$1,260.00
8 Paint Prime and two coats on walls, doors and trim.	\$2,640.00
9 Permit, dumpster and final clean	\$890.00
Total estimate, labor and materials	\$27,450.00

NOT INCLUDED

- Furnace replacement, quoted separately by the HVAC contractor
- Contents and furniture
- Mitigation and drying, billed by Lakeshore Restoration
- Any hidden damage found once walls are open

TERMS

- Valid for 30 days
- Work takes about three weeks from the start date
- 30% deposit on signing, balance on completion
- Like kind and quality to what was there before the loss

Sample document created for a software demonstration. Not a real record.

Paul Brandt

Paul Brandt, Estimator, Northshore Renovation Co.

Accepted by homeowner, date